Questions and Answers during Advertisement for
CA FLAP 03S11(1)-Reds Meadow Road

October 27, 2022

	Questions	Answers
1	Plan Sht. A9 typical section Sta 10+70 To 139+09 requires 3" HMA on 4" Aggregate Base. a. Where is demolition/ removal of the existing asphalt to be paid? b. Is pulverized asphalt suitable for embankment or aggregate base in this area?	a.) No direct payment b.) Yes, if it meets the respective specification for embankment or aggregate base.